

Item	Description	Qty.	Unit	Rate Rs.	Amount Rs.
W.5	Construction of RCC manhole internal size of 600mmX450 mm & depth< 1000mm as per detail drawing. Rate to include for excavation, necessary formwork, lifting hooks and 20mm thick cement, sand rendering in 1:2 mix trowel smooth with neat grey cement to all internal surfaces, exposed external surfaces and forming channel with 1:6 benching. Including 75mm thick RCC cover slab reinforced wth 10mm dia tor steel at 150mm c/c both ways.	1.00	nr.		
Total carried over to summary					

ORIGINAL

45
92

BILL OF QUANTITIES FOR PROPOSED RENOVATION TO FIRE STATION & TRAINING CENTER ROXY GARDEN WELLOWATTA, COLOMBO 06.

SUMMARY

BILL NO	DESCRIPTION	AMOUNT RS.
BILL NO. 1	PRELIMINARIES	
BILL NO. C	DEMOLITION	
BILL NO. D	EXCAVATION AND EARTH WORK	
BILL NO. F	CONCRETE WORK	
BILL NO. G	MASONRY WORK	
BILL NO. H	WATER PROOFING	
BILL NO K	METAL WORK	
BILL NO. L	WOOD WORK	
BILL NO. P	ROOF AND ROOF PLUMBING	
BILL NO. Q	PLUMBING AND SANITARY INSTALLATIONS	
BILL NO. S	ELECTRICAL INSTALLATION	
BILL NO. T	FLOOR AND WALL FINISHES	
BILL NO: U	GLAZING	
BILL NO. V	PAINTING	
BILL NO. W	DRAINAGE SYSTEMS	
	SUB TOTAL	
	ADD 10% CONTINGENCIES	
	TENDER PRICE (BID PRICE)	
	ADD 8% VAT	
	FINAL COST (WITH TAXES)	

SIGNATURE OF TENDERER

DATE:-

ORIGINAL

10

Section -8
DRAWINGS